



KVA	ITEM	A	B	C	D	E	F	G	H	J	K	L	M	N
45	11	49	72.5	24	48.5	48.5	36.5	35.5	27	6	5	32	8	8
75	12	49	72.5	24	48.5	48.5	36.5	35.5	27	6	5	32	8	8
150	13	49	72.5	24	48.5	48.5	36.5	35.5	27	6	5	32	8	8
225	14	49	72.5	24	50.5	50.5	36.5	35.5	27	6	5	32	8	8
300	15	49	72.5	30	58.5	58.5	36.5	35.5	27	6	5	32	8	8
500	16	49	72.5	30	60.5	67.5	36.5	35.5	27	6	5	32	8	8
750	17	63	72.5	30	62.5	69.5	36.5	35.5	27	6	5	46	8	8
1000	18	63	72.5	30	62.5	69.5	36.5	35.5	27	6	5	46	8	8
1500	19	63	72.5	30	64.5	71.5	36.5	35.5	27	6	5	46	8	8
2000	20	68	72.5	30	70.5	86.5	39.5	35.5	27	6	5	46	8	8

	ITEM	WT(LBS)	OIL(GN)
1 HV BUSHING	11	2883	180
2 LIFTING LUGS	12	2663	143
3 BOLTED COVER	13	3088	153
4 1" UPPER FILL PLUG	14	3747	178
5 PRESSURE RELIEF VALVE	15	4161	204
6 NAMEPLATE	16	5001	214
7 HINGED TOP CABINET	17	7144	346
8 LV BUSHING	19	9843	387
9 DRAIN VALVE w/SAMPLER	20	12371	523

THREE-PHASE PAD-MOUNT TRANSFORMER
45KVA THRU 2000KVA

REVISION	DESCRIPTION
SCALE: NTS	
DWN BY: BTA	DATE: 06-27-2014
	CHKD BY:
SHEET NO. 1	WORK ORDER :

LAWRENCEBURG UTILITY SYSTEMS
1607 N LOCUST AVENUE
LAWRENCEBURG, TN 38464
(931) 762-7161